BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT46564

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/12/2020-21, Date: 22.01.2021

Name of Work:Improvements to Roads and Drains at Kalidasa and Bhagat Singh Layout and Surrounding Area in ward no 05 Jakkur

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R SHIVARAM ( )	
				In Figures	In Words
1	1231.9	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. As Per the Direction of Engineer In charge of the work.	Cum	231.20	Rupees Two Hundred Thirty One and Nineteen Paise Only
2	184.79	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. As Per the Direction of Engineer In charge of the work.	Cum	5779.29	Rupees Five Thousand Seven Hundred Seventy Nine and Twenty Eight Paise Only
3	388.18	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm.As Per the Direction of Engineer In charge of the work.	Cum	7541.70	Rupees Seven Thousand Five Hundred Forty One and Seventy Paise Only
4	26.15	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3.As Per the Direction of Engineer In charge of the work.	Tonne	68234.20	Rupees Sixty Eight Thousand Two Hundred Thirty Four and Nineteen Paise Only
5	917.1	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges,curing and concrtee finished surface on both sides etc,and complete as per the directions of Enginner in charges.(Data Rate).As Per the Direction of Engineer In charge of the work.	Sqm	2451.51	Rupees Two Thousand Four Hundred Fifty One and Fifty One Paise Only
6	83.25	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for ljoints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc, (Data Rate). complete and as per the directions of Engineer in-Charge.	Sqm	5683.48	Rupees Five Thousand Six Hundred Eighty Three and Forty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

9/08

Executive Engineer
Byarayanapura Division
Yelahanka Zone BBMP